

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE


Office of the Executive Engineer, Dasarahalli Division


Schedule - B

NAME OF THE WORK: Construction of R C C Drains Abbigere Dinne Chikkasandra in Ward No.17
(SCP/TSP Works Block No.24)


Indent No: BBMP/2023-24/OW/WORK_INDENT2632/CALL-4

Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	Providing and laying 100mm thick pre-cast cover slabs over Existing Drain using M20 concrete reinforced slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including: of labour, materials, machinery, lead and lift charges etc, Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Sqm	136.26	1479.00	Rupees One Thousand Four Hundred Seventy Nine Only
2	Appendix I Additionalities for Formwork, Centering & Scaffolding 3.Foundation, Sub structure of Cross drainages 5% Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	47.69	248.00	Rupees Two Hundred Forty Eight Only
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	20.43	4704.00	Rupees Four Thousand Seven Hundred Four Only
4	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	47.69	4966.00	Rupees Four Thousand Nine Hundred Sixty Six Only


Signature of the Contractor


Executive Engineer

5	Supplying, fitting and placing TMT FE 550 / 550D Steel reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancillary operations Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	MT	2.14	62055.00	Rupees Sixty Two Thousand Fifty Five Only
6	Earth work excavation by manual means for drains, canals and similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	122.64	190.00	Rupees One Hundred Ninety Only
7	Cost of Haulage Excluding Loading and Unloading Case-1 : Surfaced Road (Taking output 10 tonnes load and lead 10 km = 100 t.km) Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	1569.79	9.00	Rupees Nine Only
8	Loading and Unloading of Stone Boulder/ Stone aggregates/Sand/Kankar/Moorum. (Tipper 10 m3) Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	122.64	93.00	Rupees Ninety Three Only


Signature of the Contractor


Executive Engineer,
Dasarahalli Division,